




EXISTING



PROPOSED

EROSION CONTROL NOTES:

- All sediment and erosion control methods shall be installed before the start of excavation and/or construction as per Standards and Specifications for Soil Erosion and Sediment Control for the District of Columbia. If an on-site inspection reveals further erosion control measures are necessary, the same shall be provided.
- All debris to be removed from site.
- Alley and/or streets shall be swept clean at all times during excavation and construction.
- All catch basins and drain area driveways shall be protected during excavation and construction.
- If any catch basin or drain becomes clogged as a result of excavation or construction it's the responsibility of the contractor to clear it.
- When sediment trap/sediment tent has reached 67% capacity, clean out of same is required.
- Any stockpiling, regardless of location on site shall be stabilized within twenty (20) days after its establishment and for the duration of the project.



Standard Symbol

V. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
College Park, Md. **STABILIZED CONSTRUCTION ENTRANCE** Standard Drawing No. 500-1

* Drainage area less than 1/2 acre.

V. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
College Park, Md. **STRAW BAILE DIKE** Standard Drawing No. 500-1

THE M.K.M. PARTNERSHIP
ARCHITECTURE • INTERIOR DESIGN

2025 EYE STREET, N.W.
WASHINGTON, D.C. 20006
TEL: (202) 223-5198

Organization of American States
INTER-AMERICAN DEFENCE BOARD BUILDING
2600 SIXTEENTH STREET, N.W., WASHINGTON, D.C.

SITE PLAN

SECTION A-A'
SECTION B-B'
SECTION C-C'
SECTION D-D'

A-1